

## Antagonistic activity of *Trichoderma* spp. against *Fusarium oxysporum* f.sp. *lycopersici* causing Fusarium Wilt of Tomato

Nitisha Gahlot\*, R.N. Bunker and Abhinav

Department of Plant Pathology, Rajasthan College of Agriculture,  
Maharana Pratap University of Agriculture and Technology, Udaipur (Rajasthan), India.

(Corresponding author: Nitisha Gahlot\*)

(Received 25 March 2022, Accepted 17 May, 2022)

(Published by Research Trend, Website: [www.researchtrend.net](http://www.researchtrend.net))

**ABSTRACT:** Tomato wilt is most devastating disease of tomato, caused by *Fusarium oxysporum* f.sp. *lycopersici* that limiting tomato production severely all over the world. Biological control with *Trichoderma* spp. has emerged as one of the most promising alternatives to the chemical control. The objective of present investigation was to examine the antagonistic activity of five different *Trichoderma* spp. viz. *Trichoderma viride*-5 (IIHR-T.V.-5), *Trichoderma viride*-PCI (T.V. P.C.I.), *Trichoderma aureoviride* (DG. A. 91-5), *Trichoderma harzianum* (J.H.H.89-2) and *Trichoderma harzianum* (ITCC- 7922/10) in laboratory conditions by applying dual culture technique, against *Fusarium oxysporum* f.sp. *lycopersici* causing tomato wilt disease. *In-vitro* test showed that all the *Trichoderma* spp. were antagonistic to the *Fusarium oxysporum* f.sp. *lycopersici*. Among all, *Trichoderma viride*-5 (IIHR-T.V.-5) was found most effective in inhibiting the mycelial growth of the pathogen and showed highest antagonistic activity, followed by *Trichoderma viride*-PCI (T.V. PCI). Application of *Trichoderma* spp. in the field not only serve as disease controlling methods but also advantageous for the vegetative growth of the plant.

**Keywords:** *Trichoderma*, tomato, wilt, *Fusarium oxysporum* f.sp. *lycopersici*.

### INTRODUCTION

Tomato (*Lycopersicon esculentum* Mill.) is also known as “poor man’s apple” and “protective food” (Mehta, 2017). It belongs to the family *Solanaceae* and viewed as one of the world's most mainstream vegetables (Pritesh and Subramanian 2011). It is an important dietary component and contains high-value in local market among horticultural crops. The fruit contains good amount of nutrients such as, vitamins A (42 µg), B<sub>1</sub> (0.037 µg), B<sub>3</sub> (0.594 µg), B<sub>6</sub> (0.08 µg), C (14mg), E (0.54 mg), K (7.9 mg), beta-carotene (449 µg) and fat (0.2 g), protein (0.9 g), dietary fibres (1.2g), lycopene (2573µg), sugars (2.6 g) water (94.5g) and carbohydrates (3.9 g), (nutritional value per 100 g) (Anon. 2020) and also contain some minerals such as calcium, phosphorus, potassium and magnesium (Kaushik *et al.*, 2011). A number of biotic and abiotic factors affect the quality and productivity of tomato in which diseases caused by fungi, bacteria, viruses and nematode, are most important. Among which *Fusarium* wilt caused by *Fusarium oxysporum* f.sp. *lycopersici* affect all tomato growing areas all over the world and causes serious economic losses (Singh *et al.*, 2015).

*Fusarium* wilt or vascular wilt disease of tomato, caused by *Fusarium oxysporum* f.sp. *lycopersici* (Sacc.) W.C. Snyder and H.N. Hans is one of the major constraints in tomato production. The disease was first reported by G.E. Masee in 1895 from England. First of all Link (1809) described the genus *Fusarium* and later classified in fungi imperfecti in the class Hyphomycetes. In India the disease was first reported by Butler, 1918 from Pusa, Bihar as *Fusarium oxysporum* f.sp. *lycopersici* according to Shiva *et al.* (2013). Snyder and Hans (2003) reported that *Fusarium oxysporum* f.sp. *lycopersici* (Sacc.) is a soil borne fungus and is specific for tomato causing wilt disease in it. Kapoor (1988) characterized disease by yellowing of leaves with wilted plants with minimum or absent of crop yield also stated that tomato wilt causes 30-40% yield loss and under favorable conditions losses increased to 80%. Biological control with *Trichoderma* spp. has emerged as one of the most promising alternatives to the chemical control. Application of *Trichoderma* spp. in the field not only serve as disease controlling methods but also advantageous for the vegetative growth of the plants.

## MATERIALS AND METHOD

### Isolation, identification and pathogenicity of *Fusarium oxysporum* f.sp. *lycopersici*

Isolation of the pathogen was done by tissue isolation method from the diseased part of the tomato plant. The fungus isolated from diseased tissues was purified by hyphal tip method and identified on the basis of cultural and morphological characters and later confirmed from Indian Type Culture Collection (ITCC), Division of Plant Pathology, IARI, New Delhi-110012. Pathogenicity of isolated culture was examined by growing tomato plants containing pathogen infested soil as per Koch's postulates.

### Antagonistic activity of *Trichoderma* spp. against *Fusarium oxysporum* f.sp. *lycopersici*

The antagonistic activity of five *Trichoderma* spp. viz., *Trichoderma viride*-5 (IIHR-T.V-5) procured from Indian Institute of Horticulture Research, Bengaluru, *Trichoderma viride*-PCI, procured from PCI: Pest Control India Pvt. Ltd., Bengaluru and three resident bioagent viz; *Trichoderma aureoviride* (DG.A. 91-5), Dungarpur, *Trichoderma harzianum* (JH.H.89-2) and *Trichoderma harzianum* (ITCC- 7922/10) procured from Udaipur were tested against wilt pathogen *Fusarium oxysporum* f.sp. *lycopersici* by using dual culture technique.

Twenty ml of PDA was transferred in each petri plate aseptically and allowed to solidify. Mycelial disc of five mm of each antagonist and test fungus were placed separately at some distance on the periphery of petri plates containing solid PDA medium. A fungus growing petri plate without antagonist was also kept as control, by placing one bit of the pathogen in the centre of the plate. Five replications of each treatment were maintained. Both inoculated and un-inoculated plates were incubated at  $28 \pm 1^\circ\text{C}$  and observed after seven days to record the growth of antagonist and test pathogen. Antagonistic activity of each bio-control agent was calculated by measuring the linear growth of the test pathogen both in dual culture and control plates. Per cent growth inhibition of pathogen and Index of antagonism were determined in each treatment by using following standard formula (Bell *et al.*, 1982):

$$I = \frac{C - T}{C} \times 100$$

Where, I= percent growth inhibition zone of pathogen

C= Growth of test fungus in control (mm)

T= Growth of test fungus in dual culture (mm).

## RESULT AND DISCUSSION

Efficacy of five *Trichoderma* spp. viz. *Trichoderma viride* -5(IIHR-T.V-5) procured from Indian Institute of Horticulture Research, Bengaluru, *Trichoderma viride*-PCI, procured from PCI: Pest Control India Pvt. Ltd., Bengaluru and three resident bioagent viz; *Trichoderma aureoviride* (DG.A. 91-5), Dungarpur, *Trichoderma harzianum* (JH.H.89-2) and *Trichoderma harzianum* (ITCC- 7922/10) procured from Udaipur were tested against *Fusarium oxysporum* f.sp. *lycopersici* (UDPA Fo-1) by using dual culture technique.

All the five bio-control agents were significantly reduced the mycelial growth of the pathogen. Results depicted that minimum mycelial growth of pathogen, 19.00mm was found in *Trichoderma viride* -5 (IIHR-T.V-5) with maximum per cent growth inhibition 78.88% followed by *T. viride*-PCI (T.V.-PCI) with 22.60mm mycelial growth and 74.82% growth inhibition. Further, bio-agent *T. harzianum* (JH.H.89-2) showed 26.30mm mycelial growth with 70.77% growth inhibition of pathogen. Maximum mycelial growth of pathogen (30.00mm) was found in *T. aureoviride* (DG.A. 91-5) with minimum per cent growth inhibition (66.66%) followed by *T. harzianum* (ITCC- 7922/10) which showed 29.00mm mycelial growth and 67.77% growth inhibition of pathogen (Table 1, Plate1, Fig. 1).


The present findings are in conformity with Bhujbal *et al.* (2021), they tested antagonistic activity of six different bio-agents viz. *Trichoderma viride*, *T. harzianum*, *T. hamatum*, *T. koningii*, *Bacillus subtilis* and *Pseudomonas fluorescens* in *in vitro* conditions against *Fusarium oxysporum* f.sp. *lycopersici*. Among them, *T. viride* (84.84% growth inhibition) was found superior followed by *T. harzianum* (72.54% growth inhibition) and *T. hamatum* (69.93% growth inhibition) to inhibit fungal growth of pathogen. Similarly, Kumar *et al.* (2021) tested antagonistic activity of five bio control agents viz. *T. harzianum*, *T. viride*, *Chaetomium globosum*, *Bacillus subtilis* and *Pseudomonas fluorescens* by employing dual culture technique against *Fusarium oxysporum* f.sp. *lentis* causing vascular wilt of lentil. Among them, *T. viride* (76.25% growth inhibition) found significantly superior followed by *Chaetomium globosum* (75% growth inhibition) after 144 hours of incubation. Reports of Sara *et al.* (2018); Devi *et al.* (2013) also support the present findings. Bio-control through *Trichoderma* spp. has great potential to reduce the disease in lab as well as in field conditions. Akrami and Yousefi (2015) stated that *T. harzianum*, *T. aspergillum* and *T. virens* has more protective effect against *Fusarium solani* and *Fusarium oxysporum*.

**Table 1: Effect of different bio-control agents on mycelial growth of *Fusarium oxysporum* f.sp. *lycopersici* in vitro.**


Sr. No.	Bio-control agents		Mycelial growth (mm*)		Per cent Growth inhibition*
		Isolate code	Control	Dual culture	
1.	<i>T. viride</i>	IIHR-T.V.-5	90.0	19.00	78.88 (62.65)
2.	<i>T. viride</i>	T.V. P.C.I.	90.0	22.60	74.82 (59.88)
3.	<i>T. aureoviride</i>	D.G A. 91-5	90.0	30.00	66.66 (54.73)
4.	<i>T. harzianum</i>	J.H.H. 89-2	90.0	26.30	70.77 (57.27)
5.	<i>T. harzianum</i>	ITCC-7922/10	90.0	29.00	67.77 (55.39)
SEM±			1.981	0.542	0.548
CD at 5%			6.103	1.671	1.689
C.V. (%)			3.81	3.70	1.64

\*Mean of four replications

Figure in parentheses are arcsine  $\sqrt{\text{per cent angular transformed values}}$



**Plate 1: Antagonistic activity of *Trichoderma* spp. against *Fusarium oxysporum* f.sp. *lycopersici* by Dual culture method.**



**Fig. 1.** Antagonistic activity of *Trichoderma* spp. against *Fusarium oxysporum* f.sp. *lycopersici* by Dual culture method.

## CONCLUSION

Hence, from the present study and results, it is concluded that in *in vitro* efficacy of biological control agents *Trichoderma viride-5* was found to be most effective for the suppression of mycelia growth of tomato wilt pathogen *Fusarium oxysporum* f.sp. *lycopersici* followed by *Trichoderma viride-PCI*. The use of bio-control agent has proved economic and ecological alternative method to manage different plant disease in effective manner.

**Acknowledgement.** The authors are thankful to Department of Plant Pathology, Rajasthan College of Agriculture, Udaipur (Rajasthan), for providing the facilities to carry out the laboratory assay and scientific assistance in terms of study.

**Conflict of interest.** None.

## REFERENCES

- Akrami, M and Yousefi, Z. (2015). Biological control of *Fusarium* wilt of tomato (*Solanum lycopersicum*) by *Trichoderma* spp. as antagonist fungi. *Biological Forum-An international Journal*, 7(1): 887-892.
- Anonymous (2020). Horticultural Statistics at a Glance. Page-203, agricoop.nic.in
- Bell, D. K., Wells, H. D. and Markham, C. R. (1982). *In vitro* antagonism of *Trichoderma* spp. against six fungal pathogens. *Phytopathology*, 72: 379-382.
- Bhujbal, M., Gawade, R., Bachkar, D., Deokar, C. and Daingade, N. (2021). *In vitro* efficacy of different biological agents against *Fusarium oxysporum* f.sp. *lycopersici* causing wilt of tomato. *Journal of Entomology and Zoology Studies*, 9(1): 486-489.
- Devi, T. N., Linthoingambi, W. and Singh, M. (2013). Evaluation of *Trichoderma* species against *Fusarium oxysporum* f.sp. *lycopersici* for biological control of tomato wilt. *Indian Phytopathology*, 66: 81-87.
- Kaushik, S. K., Tomar, D. S., Dixit A. K. (2011). Genetics of fruit yield and it's contributing characters in tomato

(*Solanum lycopersicum* L.). *Journal of Agricultural Biotechnology and Sustainable Development*, 3(10): 209-213.

- Kumar, A. (2021). Management of *Fusarium* wilt of tomato using *Trichoderma harzianum*. *International Journal of Research and Analytical Reviews*, 6(1): 9-16.
- Kapoor, I. J. (1988). Fungi involved in tomato wilt syndrome in Delhi, Maharashtra and Tamil Nadu. *Indian Phytopathology*, 41(2): 208-213.
- Link, H. F. (1809). Observations in Ordines Plantarum Naturales, Mag. Ges. naturf. Freunde, 3: 3-23.
- Massee, G. (1895). The 'sleepy disease' of tomatoes. *Garden Chronicles*, 3(17): 707-708.
- Mehta, R. (2017). History of tomato (Poor man's apple). *Journal of Humanities and Social Science (IOSR-JHSS)*, 22(8): 31-34.
- Pritesh, P. and Subramanian, R. B. (2011). PCR based method for testing *Fusarium* wilt resistance of tomato. *African Journal of Basic and Applied Sciences*, 3(5): 219-222.
- Sara, Z., Mourad, S. M., Ammar, O. and Wahiba, H. (2018). The effect of *in vitro* and *in vivo* *Trichoderma* spp. (TR2) on the reduction of infection of the tomato variety (Elgon) contaminated with *Fusarium oxysporum* f.sp. *lycopersici*. *World Journal of Environmental Bioscience*, 7(4): 112-118.
- Shiva N. G., Gomathi, S. Karthika, S., Ramya, B., Senathipathi, P., Senthil, Surendar, K. K. and Kumar, S. R. (2013). Physiological effects of *Pseudomonas fluorescens* on tomato, *International Journal of Horticulture*, 3(18): 104-108.
- Singh, R., Biswas, S. K., Nagar1, D., Singh, J., Singh, M., and Mishra, Y. K. (2015). Sustainable integrated approach for management of *Fusarium* wilt of tomato caused by *Fusarium oxysporum* f.sp. *lycopersici* (Sacc.) Synder and Hansen. *Sustainable Agriculture Research*, 4(1): 138-147.
- Snyder, W. C. and Hans, H. N. (2003). Introduction, identification, isolation of *Fusarium oxysporum* f.sp. *lycopersici*. Soil Borne Plant Pathogen. Class project, Spring pp. 728.

**How to cite this article:** Nitisha Gahlot, R.N. Bunker and Abhinav (2022). Antagonistic Activity of *Trichoderma* spp. Against *Fusarium oxysporum* f.sp. *lycopersici* causing *Fusarium* Wilt of Tomato. *Biological Forum – An International Journal*, 14(2): 1000-1003.